KADUR DIVISION.

The 7th January 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur division, up to 5th February 1897, for constructing a Female Dispensary with wards for in-patients and quarters for the Hospital Assistant at Chikmagalur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1897.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chikmagalur between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Female Dispensary with wards for in-patients and quarters for the Hospital Assistant at Chikmagalur," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items of work.	*Per.*	*Quantity.*
Earthwork excavation	C. yd.	120
Rough stone in mud	C. ft.	288
Concrete in surki mortar	"	321
Burnt stone in chunam	"	4,424
Burnt brick in chunam	"	6,949
Do upper storey	"	1,872
Do arch work	"	44
Burnt brick in mud	"	526
Burnt stone slabs	Sq. ft.	947
Do for flagging with cement pointing and sand below it	"	898
Quoin work	R. ft.	192
Cornice burnt brick in chunam and plaster over it	"	293
Coping with chunam plastering	"	231
Teak wood work	C. ft.	520
Do plain eave boards	R. ft.	324
Teak wood railing as per plan (ornamental)	Sq. ft.	102
Do screen with door as per plan	"	114
Do plank with reapers to floor the terrace	"	642
Roofing with 1st class Mangalore tiles and teak reapers, &c., complete	Sqrs.	35·16
Ridging with Mangalore tiles	R. ft.	227
Ventilating tiles	Each	16
Terracing with 1 course of brick and 2 course of flat tiles with chunam plastering.	Sqr.	5·99
Plastering with chunam	"	127·60
Pointing with chunam	"	6·76
White washing 2 coats	"	87·07
Color washing do	"	56·00
Flooring with Mangalore tiles and 6" sand under tiles with cement pointing, &c.	"	8·76
Teak wood doors (circular) as per plan with hinges rimlock, &c., complete	Sq. ft.	30
Flooring with gravel	C. yd.	2
Teak wood door battened large with frame do ($3\frac{1}{4}' \times 6\frac{1}{4}'$)	Sq. ft.	387
Do small do ($3' \times 6'$)	"	126
Teak wood window with iron bar glazed shutter inside and battened shutter outside with frames, &c. ($3\frac{1}{4}' \times 4\frac{1}{2}'$)	"	299
Do do ($2\frac{1}{2}' \times 3'$)	"	45
Do do ($2' \times 2\frac{1}{2}'$)	"	5
Wood oiling	Sqr.	45·00
Chocolate painting for doors and windows	"	25·67
Zinc sheets for the valley above hip rafters	Lump sum.	
Iron pipe 1" diameter	"	..
Tarring	"	..
Coir matting	Sqr.	9·00
Iron gate shutter lock and keys, &c.	No.	1
Stair case wooden as per plan	Lump sum.	